

**KEMPER MILITARY SCHOOL K-BARRACKS BUILDING SITE CLEANUP  
 BID FORM – PROPOSAL**

SUBMITTED BY \_\_\_\_\_  
 (Company Name)

Pursuant to and in accordance with the above stated Invitation for Bid, the undersigned hereby declares that they have examined the bid documents and specifications for the item(s) listed below.  
 The undersigned proposes and agrees, if their Bid is accepted to furnish the item(s) submitted below, including delivery to the Owner in accordance with the delivery schedule indicated below and according to the prices products/services information submitted.

Item Number	Description	Unit	Estimated Quantity	Unit Price	Extended Amount (Total)
<b>BASE BID ITEMS</b>					
<b>ASBESTOS-CONTAINING MATERIALS</b>					
1	12" x 12" Vinyl Tile/Mastic – Brown (3 <sup>rd</sup> Floor Rooms)	Sq. ft.	9,350	\$	\$
2	12" x 12" Vinyl Tile/Mastic – Gray (3 <sup>rd</sup> Floor Hallway)	Sq. ft.	1,650	\$	\$
3	12" x 12" Vinyl Tile/Mastic – White (Room 339)	Sq. ft.	35	\$	\$
4	Ceiling Texture (1 <sup>st</sup> , 2 <sup>nd</sup> and 3 <sup>rd</sup> Floor Rooms)	Sq. ft.	28,000	\$	\$
5	12" x 12" Vinyl Tile – Brown (Throughout 2 <sup>nd</sup> Floor)	Sq. ft.	11,000	\$	\$
6	12" x 12" Vinyl Tile – Brown (Throughout 1 <sup>st</sup> Floor)	Sq. ft.	11,000	\$	\$
7	Vibration Dampener (Storage Room)	each	2	\$	\$
8	Mudded Fitting (Boiler Room)	each	250	\$	\$
9	Magblock Duct Insulation (Boiler Room)	Sq. ft.	800	\$	\$
10	Boiler Opening Mud (Boiler Room)	Lin. Ft.	15	\$	\$

Item Number	Description	Unit	Estimated Quantity	Unit Price	Extended Amount (Total)
11	Large Horizontal Water Tank Insulation (Boiler Room)	Sq. ft.	175	\$	\$
12	Small Upright Water Tank Insulation (Boiler Room)	Sq. ft.	150	\$	\$
13	Boiler Tanks Insulation (Boiler Room)	Sq. ft.	500	\$	\$
14	Spray-on Fireproofing (Boiler Room Ceiling)	Sq. ft.	2,400	\$	\$
15	12" x 12" Vinyl Tile/Mastic – White (Basement)	Sq. ft.	3500	\$	\$
16	12" x 12" Vinyl Tile/Mastic – Brown (Basement)	Sq. ft.	3,500	\$	\$
17	Drywall (Basement)	Sq. ft.	650	\$	\$
<b>REMEDIAL ACTION FINAL REPORT</b>					
18	Project Health & Safety Plan, QAPP, and any other items necessary to finalize plan per MDNR/BVCP	Unit	1	\$	\$
19	Field Mobilization/Demobilization, Regulatory Notification and Permitting	Unit	1	\$	\$
20	Preparation of the Remedial Action Final Report	Unit	1	\$	\$
<b>Base Bid Item Total</b>				\$	

Notes:

Please note that the site's Remedial Action Plan further details the materials/items to be addressed during the cleanup activities. Additionally, the Remedial Action Plan details confirmation sampling associated with the cleanup. Cost associated with the confirmation sampling should be incorporated into the rates/costs listed in the table above.